

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

Beverly Eaves Perdue
GOVERNOR

EUGENE A. CONTI, JR.
SECRETARY

October 26, 2009

NOTICE TO PROSPECTIVE BIDDERS

Subject: Invitation to Bid

Project Description: Concrete Bridge Enhancements, Ornamental Fencing, Milling, Resurfacing, Sidewalk, Curb & Gutter, Planters, Pavement Markings and Markers.

(WBS 45065.3.ST1)

EB-5119

Gaston County

The North Carolina Department of Transportation is requesting bids for milling, resurfacing, curb & gutter, sidewalk, ornamental fencing, planters, pavement markings and markers. The Contractor is to furnish labor, material, equipment, and traffic control.

The availability date for this project is January 4, 2010. The completion date is September 30, 2010.

**A Mandatory Pre-Bid Conference is set for November 19, 2009 at the
Gastonia City Hall,
Council Conference Room 2nd Floor,
181 South Street
Gastonia, NC 28052 at 10:00 AM.**

Sealed bids must be received in the Division Engineer's Office at 1710 East Marion Street by **10:00 A.M. Thursday December 10, 2009**. Bids must be submitted on the official bid sheet included in the proposal and display the following statement on the front of the envelope:

**QUOTATION FOR WBS 45065.3.ST1 (EB-5119) TO BE OPENED AT 10:00 A.M.
ON THURSDAY December 10, 2009.**

The North Carolina Department of Transportation, in accordance with the provisions of Title VI of the Civil Rights of 1964 (78 Stat.252) and the Regulations of the Department of Transportation (49 C.F.R., Part 21), issued pursuant to such act, hereby notifies all bidders that it will affirmatively insure that the contract entered into pursuant to this notice will be awarded to the lowest responsible bidder without discrimination on the grounds of sex, race, color, or national origin.

Proposals may be obtained at the Division Office located at 1710 East Marion Street in Shelby or by calling Bryan Sowell at 704-480-9047 or Ron Humphries at 704-480-9046. Please refer to the Work Order referenced when making requests.

Sincerely,

Mr. M.L. Holder, PE
Division Engineer, Twelfth Division

bks

cc: Ms. Chelsea Andujar, AGC
Mr. Lex Garey, PE
Mr. Gary Spangler

North Carolina Department of Transportation BID FORM

WBS

45065.3.ST1

EB-5119

ELEMENT:

DESCRIPTION: Downtown Thread Trail Bicycle Pedestrian Connector and Marietta Street Bridge Improvement Project. Concrete Bridge Enhancements, Ornamental Fencing, Milling, Resurfacing, Sidewalk, Curb & Gutter, Planters, Pavement Markings and Markers.

COUNTY:

GASTON

ITEM	SECT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	AMOUNT BID
1.	800	MOBILIZATION	1	LS		
2.	200	CLEARING & GRUBBING	0.25	ACRE		
3.	230	BORROW EXCAVATION	700	CY		
4.	250	CONCRETE REMOVAL	450	SY		
5.	250	REMOVAL OF EXIST ASPHALT PAVEMENT	85	SY		
6.	250	BRICK PAVER REMOVAL	56	SY		
7.	300	FOUNDATION CONDITION MATERIAL, MINOR STRUCTURES	20	TONS		
8.	310	12" RC PIPE CULVERT, CLASS III	8	LF		
9.	310	15" RC PIPE CULVERT, CLASS III	120	LF		
10.	310	18" RC PIPE CULVERT, CLASS III	16	LF		
11.	340	PIPE REMOVAL (18" FES)	1	EA		
12.	545	INCIDENTAL STONE BASE	50	TON		
13.	607	INCIDENTAL MILLING	500	SY		
14.	607	MILLING ASPHALT PAVEMENT, 1.5" DEPTH	4100	SY		
15.	610	ASP CONC SURFACE CRS, TYPE S9.5B	380	TON		
16.	610	ASP CONC BINDER CRS, TYPE I19.0B	48	TON		
17.	610	ASP CONC BASE CRS, TYPE B25.0B	75	TON		
18.	620	ASP BINDER FOR PLANT MIX PG 64-22	30	TON		
19.	840	FRAME w/GRATE & HOOD STD 840.03, TYPE E	1	EA		
20.	840	MASONRY DRAINAGE STRUCTURE	3	EA		
21.	840	DI FRAME & GRATE, STD. 840.16	2	EA		
22.	SP	CONVERT EXISTING CATCH BASIN TO JUNCTION BASIN, STD 840.32	1	EA		
23.	840	FRAME WITH COVER, STD. 840.54	1	EA		
24.	846	2'-6" CONCRETE CURB & GUTTER	130	LF		
25.	848	4" CONCRETE SIDEWALK	965	SY		
26.	848	CONCRETE WHEELCHAIR RAMP	7	EA		
27.	852	5" MONO CONCRETE ISLAND	70	SY		
28.	858	ADJUSTMENT OF MANHOLES	1	EA		
29.	1110	WORK ZONE SIGNS (PORTABLE)	80	SF		
30.	1110	WORK ZONE SIGNS (STATIONARY)	232	SF		
31.	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	82	SF		
32.	1115	FLASHING ARROW PANEL, TYPE C	2	EA		
33.	1130	DRUMS	200	EA		
34.	1145	BARRICADES (TYPE III)	56	LF		
35.	1205	THERMO PVT MRK LINES 12"120 MIL	1860	LF		
36.	1205	THERMO PVMT MRK LINES 4"90MIL	400	LF		
37.	1205	THERMO PVMT MRK LINES 4"120MIL	3285	LF		
38.	1205	THERMO PVMT MRKS LINES 24"120MIL	135	LF		

39.	1205	THERMO PVMT SYMBOLS 90 MIL	35	EA		
40.	1205	REMOVAL OF THERMO PVMT MARKING LINES	400	LF		
41.	1205	REMOVAL OF THERMO PVMT MARKING SYMBOLS	10	EA		
42.	1413	PORTABLE LIGHTING	1	LS		
43.	1605	TEMPORARY SILT FENCE	1000	LF		
44.	1610	STONE FOR EROSION CONTROL, CLASS A	40	TONS		
45.	1610	SEDIMENT CONTROL STONE	10	TONS		
46.	1660	SEEDING & MULCHING	1	ACR		
47.	SP	CAST IN PLACE DETECTABLE WARNING DOMES FOR EXISTING WHEELCHAIR RAMPS	12	EA		
48.	SP	PATCHING EXISTING PAVEMENT	92	TON		
49.	SP	ORNAMENTAL WELDED STEEL FENCE	125	LF		
50.	SP	PLANTING SOIL MIX	45	CY		
51.	SP	PLANTING BED MULCH	40	SY		
52.	SP	DECORATIVE ASPHALT CROSSWALKS	9200	SF		
53.	SP	LED CROSS-WALK WARNING SYSTEM	1	LS		
54.	SP	CMU PLANTERS (TYPE 1A,1B)	1	LS		
55.	SP	CMU PLANTERS (TYPE V)	1	LS		
56.	SP	LIGHTED BOLLARDS (<i>INSTALLATION ONLY MATERIAL SUPPLIED BY CITY OF GASTONIA</i>)	3	EA		
57.	SP	THREAD TRAIL MEDALLIONS (<i>INSTALLATION ONLY MATERIAL SUPPLIED BY CITY OF GASTONIA</i>)	7	EA		
58.	SP	WATER FILLED BARRIER	230	LF		

Traffic Signal & Electrical Items

59.	SP	RELOCATE EXISTING STREET LIGHT (LONG AVE)	6	EA		
60.	SP	BORE AND JACK (16 STEEL CASING W/ CONDUITS)	135	LF		
61.	SP	TRENCH POLYETHYLENE CONDUIT (SCH 80) (2")	2200	LF		
62.	SP	TRENCH POLYETHYLENE CONDUIT (SCH 80) (4")	220	LF		
63.	SP	TRENCH POLYETHYLENE CONDUIT (SCH 80) (6")	215	LF		
64.	SP	TRACER WIRE	2635	LF		
65.	SP	FIBERGLASS CONC UNDERGROUND VAULT (48"x30")	2	EA		
66.	SP	FIBERGLASS CONC UNDERGROUND VAULT (48"x48")	1	EA		
67.	SP	SIGNAL CABLE (16 GAUGE, 7 CONDUCTOR WIRE)	4000	LF		
68.	SP	JUNCTION BOX (STANDARD SIZE) ELECTRIC	4	EA		
69.	SP	JUNCTION BOX (STANDARD SIZE) TRAFFIC	2	EA		
70.	SP	JUNCTION BOX (OVERSIZE) TRAFFIC	3	EA		
71.	1722	2" RISER WITH HEAT SHRINK TUBING	1	EA		
72.	1722	CONTROLLER WITH CABINET (BLACK)	1	EA		
73.	SP	SIGNAL CABINET FOUNDATION	1	EA		
74.	SP	CABINET BASE ADAPTER	1	EA		
75.	SP	UTILITY BASE AND PED FOR 332 (BLACK)	1			
76.	SP	CABINET BASE EXTENDER	1	EA		
77.	SP	DETECTOR CARD	1	EA		
78.	SP	AERIAL SPLICE ENCLOSURE	1	EA		
79.	SP	TERMINAL SPLICE BOX	1	EA		
80.	SP	FIBER OPTIC MODEM	1	EA		
81.	SP	FIBER OPTIC SPLICE TRAY	1	EA		
82.	1732	FIBER OPTIC TRANSRECEIVER, DROP & REPEAT	1	EA		

83.	SP	INSTALLATION OF 3-SECT 12" SIGNAL HEAD w/LEDs PAINTED BLACK w/VISORS (MATERIAL SUPPLIED BY CITY OF GASTONIA)	7	EA		
84.	SP	INSTALLATION 5-SECT 12" SIGNAL HEAD w/LEDs PAINTED BLACK w/VISORS (MATERIAL SUPPLIED BY CITY OF GASTONIA)	1	EA		
85.	SP	INSTALLATION ASTRO BRACKETS FOR 3-SECT SIGNAL HEADS w/96" CABLE (MATERIAL SUPPLIED BY CITY OF GASTONIA)	7	EA		
86.	SP	INSTALLATION ASTRO BRACKETS FOR 5-SECT SIGNAL HEADS w/96" CABLE (MATERIAL SUPPLIED BY CITY OF GASTONIA)	1	EA		
87.	SP	PEDESTRIAN SIGNAL HEAD (16")	8	EA		
88.	1743	SIGNAL PEDESTAL WITH FOUNDATION (PEDESTRIAN)	2	EA		
89.	SP	4.5"x10' SPUN ALUMINUM PED POLE (BLACK)	2	EA		
90.	SP	ALUMINUM PEDESTRIAN BASE WITH ANCHOR BOLTS (BLACK)	2	EA		
91.	SP	ACORN CAP FOR 4.5" OD POLE	2	EA		
92.	SP	TRAFFIC SIGNAL TWIN MAST ARM (MAST ARM SUPPLIED BY CITY OF GASTONIA)	2	EA		
93.	SP	NEW ELECTRIC SERVICE	1	EA		
94.	SP	DROP CABLE (6 FIBER)	200	LF		
95.	SP	COMMUNICATION CABLE (12 FIBER)	100	LF		

Structure Items

96.	SP	REMOVAL OF 3-BAR METAL RAILS	1	LS		
97.	SP	EPOXY REINFORCING STEEL (SIDEWALK)	3247	LB		
98.	SP	CLASS AA SAND-LIGHTWEIGHT CONCRETE (SIDEWALK)	42.7	CY		
99.	SP	FENCE & HANDRAIL METALWORK	1	LS		
100.	SP	COLUMNS	1	LS		
101.	SP	LIGHT BOLLARDS (INSTALLATION ONLY) (MATERIAL SUPPLIED BY CITY OF GASTONIA)	1	LS		
102.	SP	PLANTERS	1	LS		
103.	SP	BARRIER RAIL	192.7	LF		
104.	SP	RAILROAD FLAGMAN	1	LS		

NOTE: CONTRACT QUANTITIES ARE APPROXIMATE AND USED FOR DETERMINING THE LOWEST RESPONSIBLE BIDDER ONLY. NO MINIMUM OR MAXIMUM AMOUNT OF WORK IS GUARANTEED UNDER THIS CONTRACT.

***TOTAL BID FOR
PROJECT:*** _____

CONTRACTOR _____

ADDRESS _____

Federal Identification Number _____
Number

Contractors License _____

Authorized Agent _____

Title _____

Signature _____


Date

Witness _____

Title _____

Signature _____

Date



Corporate Seal